

SECTION 1 : SABS 1200 A - GENERAL

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
1.1	8.3	FIXED-CHARGE AND VALUE RELATED ITEMS				
1.1.1	8.3.1	Contractual Requirements	Sum	1		
	8.3.2	Establishment of Facilities on the Site				
	8.3.2.1	Facilities for Engineer				
1.1.2	PSAB 3.2	a) Furnished offices (1No.)	Sum	1		
1.1.3		b) Telephone	Sum	1		
1.1.4		c) Nameboards (2 No.)	Sum	1		
	8.3.2.2	Facilities for Contractor				
1.1.5		a) Offices and storage sheds	Sum	1		
1.1.6		b) Workshops	Sum	1		
1.1.7		c) Laboratories	Sum	1		
1.1.8		d) Living accommodation	Sum	1		
1.1.9		e) Ablution and latrine facilities	Sum	1		
1.1.10		f) Tools and equipment	Sum	1		
1.1.11		g) Water supplies, electric power and communications	Sum	1		
1.1.12		h) Dealing with water (see 5.5)	Sum	1		
1.1.13		i) Access (see 5.8)	Sum	1		
1.1.14		j) Plant	Sum	1		
1.1.15	8.3.3	Other Fixed-charge Obligations	Sum	1		
1.1.16	8.3.4	Removal of Site Establishment	Sum	1		
1.1.17	PSA 8.3.5	Provision of a Materials Guarantee	Sum	1		
	PSA 8.4.6	Compliance with the OHS Act (1993, as amended), the Construction Regulations (2014) and the Particular Safety Specification:				
1.1.18	PSHSS 6.1.2; CR 5 (1)(l)	i) Preparation of the Contractor's site specific Health and Safety Plan	Sum	1		
1.1.19	CR 7(1)(b)	ii) Principal Contractor's initial obligations in respect of the Occupational Health and Safety Act and Construction Regulations	Sum	1		
	GSR 2; PSHSS 7.7	iii) Provision of EPWP Branded SABS Personal Protective Equipment				
1.1.20		(a) Hard Hats	No	70		
1.1.21		(b) Reflective vests	No	70		
1.1.22		(c) Protective foot wear	No	70		
1.1.23		(d) Corded Earplugs	No	200		
1.1.24		(e) Dust masks FFP2	No	200		
1.1.25		(g) Gloves	No	200		
1.1.26		(h) Goggles	No	200		
CARRIED FORWARD						

SECTION 1 : SABS 1200 A - GENERAL

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
		BROUGHT FORWARD				
	CR 7(1)(g);	iv) Cost of medical certificates and medical surveillance				
1.1.27	PSHSS 7.2	(a) Initial (baseline) medical examinations	No	30		
1.1.28		(b) Exit medical examinations	No	30		
	PSHSS 7.14	v) Fall Protection				
1.1.29		a) Lifeline & anchorage	No	2		
1.1.30		b) Safety Harnesses	No	5		
1.1.31		c) Rescue Kit	No	1		
		vi) Occupational Hygiene Survey				
1.1.32	NIHL 6; PSHSS 7.3	(a) Establishment of noise zones (plant)	Sum	1		
1.1.33		(b) Compliance with Amendment of the Occupational Exposure Control Limit for Silica in Table 1 of the Hazardous Chemical Substances including air sampling and analysis	Sum	1		
1.1.34	PSA 8.4.7	Compliance with EMP and EMPr	Sum	1		
1.2	8.4	TIME-RELATED ITEMS				
1.2.1	8.4.1	Contractual Requirements		1		
	8.4.2	Operation and Maintenance of Facilities on Site, for Duration of Construction, except where otherwise stated				
	8.4.2.1	Facilities for Engineer				
1.2.2		a) Furnished offices (1No.)		1		
1.2.3	PSAB 8.4.1	b) Telephone	Sum	1		
1.2.4		c) Nameboards (2 No.)	Sum	1		
1.2.5		d) Survey assistants and materials	Sum	1		
	8.4.2.2	Facilities for Contractor				
1.2.6		a) Offices and storage sheds	Sum	1		
1.2.7		b) Workshops	Sum	1		
1.2.8		c) Laboratories	Sum	1		
1.2.9		d) Living accommodation	Sum	1		
1.2.10		e) Ablution and latrine facilities	Sum	1		
1.2.11		f) Tools and equipment	Sum	1		
1.2.12		g) Water supplies, electric power and communications	Sum	1		
1.2.13		h) Dealing with water (see 5.5)	Sum	1		
1.2.14		i) Access (see 5.8)	Sum	1		
1.2.15		j) Plant	Sum	1		
1.2.16	8.4.3	Supervision for duration of Construction	Sum	1		
CARRIED FORWARD						

SECTION 1 : SABS 1200 A - GENERAL

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
		BROUGHT FORWARD				
1.2.17	8.4.5	Other Time-related Obligations	Sum	1		
	PSA 8.4.6	Compliance with the OHS Act (1993, as amended), the Construction Regulations (2014) and the Particular Safety Specification:				
1.2.18	CR 5(1)(g)	i) Principal Contractor's time related obligations in respect of the Occupational Health and Safety Act and Construction Regulations	month	12		
1.2.19	CR 8(5); PSHSS 6.1.5	ii) Provision of a full- time SACPCMP registered Construction Health and Safety Officer	month	12		
1.2.20		iii) Provision of a part-time assistant SACPCMP Candidate Construction Health and Safety Officer for Subcontractor Management & Assistance	month	12		
		iv) OH&S Legal Compliance Training - SAQA UNIT STANDARD				
1.2.21	GSR 3(5); PSHSS 7.5	a) First Aid	No	1		
1.2.22	PSHSS 6.1.7	b) H&S Representative	No	1		
1.2.23	PSHSS 7.14	c) Working at height & rescue operations	No	20		
1.2.24	CR 29(h)	d) Basic Fire Fighting	No	1		
1.2.25	PSHSS 6.1.3/4	e) Safety for Supervisors	No	2		
1.2.26	PSHSS 7.13	f) Temporary Works Training	No	20		
1.2.27	SANS 10085; PSHSS 7.13	g) Scaffolding	No	5		
1.2.28	PSHSS 7.10	h) Plant Operators	No	5		
1.2.29	PSHSS 6.1.6	i) Temporary Roadworks Signage	Sum	1		
1.2.30	PSHSS 7.17	j) Excavation Safety - Supervisors	No	12		
1.2.31		k) Other	Sum	1		
1.2.32	GSR 3; PSHSS 7.5	v) Provision of First Aid Boxes to GSR requirements	No	3		
1.2.33	GMR 18; PSHSS 7.13	vi) Lifting Equipment Inspection by AIA	Sum	1		
1.2.34	PSHSS 7.13	vii) Temporary Works Designs, Inspections and Approval	Sum	1		
1.2.35	CR 7(1)(c) (e)	viii) Submission of a Health and Safety File	Sum	1		
1.2.36	PSA 8.4.7	Compliance with EMP and EMPr	Sum	1		
1.2.37	PSA 8.4.8	Supervision of Subcontractor	Sum	1		
CARRIED FORWARD						

## SECTION 1 : SABS 1200 A - GENERAL

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
1.3	8.5	BROUGHT FORWARD SUMS STATED PROVISIONALLY BY ENGINEER (Subclause 8.1.2.1 (d))				
1.3.1		Community Liason Officer	Prov. Sum	1	84 000.00	84 000.00
1.3.2		Overheads, charges and profit on 1.3.1 above	%	84000		
1.3.3		Allowance for Nominated Environmental Control Officer	Prov. Sum	0	110 000.00	0.00
1.3.4		Overheads, charges and profit on 1.3.3 above	%	0		
1.3.5		Allowance for Nominated Health and Safety Officer	Prov. Sum	0	230 000.00	0.00
1.3.6		Overheads, charges and profit on 1.3.5 above	%	0		
1.3.7		Allowance for Nominated ISD Officer	Prov. Sum	0	115 000.00	0.00
1.3.8		Overheads, charges and profit on 1.3.7 above	%	0		
1.3.9		Additional Tests required by Engineer	Prov. Sum	1	50 000.00	50 000.00
1.3.10		Overheads, charges and profit on 1.3.9 above	%	50000		
1.3.11		Allowance for additional survey	Prov. Sum	1	50 000.00	50 000.00
1.3.12		Overheads, charges and profit on 1.3.11 above	%	50000		
1.3.13		Allowance for relocation of existing services	Prov. Sum	1	100 000.00	100 000.00
1.3.14		Overheads, charges and profit on 1.3.13 above	%	100000		
1.3.15		Allowance for connections to existing infrastructure	Prov. Sum	1	50 000.00	50 000.00
1.3.16		Overheads, charges and profit on 1.3.15 above	%	50000		
1.3.17		Allowance for River Crossings	Prov. Sum	2	150 000.00	300 000.00
1.3.18		Overheads, charges and profit on 1.3.17 above	%	150000		
1.3.19		Allowance for lightning protection at Reservoir	Prov. Sum	1	50 000.00	50 000.00
1.3.20		Overheads, charges and profit on 1.3.19 above	%	50000		
1.3.21		Allowance for HIV awareness and training	Prov. Sum	1	10 000.00	10 000.00
1.3.22		Overheads, charges and profit on 1.3.21 above	%	10000		
CARRIED FORWARD						

## SECTION 1 : SABS 1200 A - GENERAL

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
		BROUGHT FORWARD				
		Expanded Public Works Programme (EPWP)				
1.3.23		Allowance for training on targeted labour	Prov. Sum	1	100 000.00	100 000.00
1.3.24		Overheads, charges and profit on 1.3.23 above	%	100000		
1.3.25		Transportation and accomodation of workers for training where it is not possible to undertake in close proximity	Prov. Sum	1	10 000.00	10 000.00
1.3.26		Overheads, charges and profit on 1.3.25 above	%	10000		
1.3.27		Equipment for the Engineer	Prov. Sum	1	150 000.00	150 000.00
1.3.28		Overheads, Charges and Profit on item 1.3.27 above	%	150000		
1.3.29		Allowance for Civil Engineering Student / Trainee	Prov. Sum	1	96 000.00	96 000.00
1.3.30		Overheads, Charges and Profit on item 1.3.29 above	%	96000		
1.3.31		Transportation (including fuel) for the Engineer for the duration of the contract.	Prov. Sum	1	420 000.00	600 000.00
1.3.32		Overheads, Charges and Profit on item 1.3.31 above	%	420000		
1.3.33		Accomodation for the Engineer for the duration of the contract.	Prov. Sum	1	125 000.00	125 000.00
1.3.34		Overheads, Charges and Profit on item 1.3.33 above	%	125000		
1.3.35		Cellphone allowance for the Engineer for the duration of the contract.	Prov. Sum	1	50 000.00	50 000.00
1.3.36		Overheads, Charges and Profit on item 1.3.35 above	%	50000		
	PSA 8.7	DAYWORK (See 8.1.2.1 (d) )				
1.3.37		a) Labour	Prov. Sum	1	100 000.00	100 000.00
1.3.38		Overheads, charges and profit on item 1.3.33 above	%	100000		
1.3.39		b) Materials	Prov. Sum	1	100 000.00	100 000.00
1.3.40		Overheads, charges and profit on item 1.3.35 above	%	100000		
1.3.41		c) Plant	Prov. Sum	1	100 000.00	100 000.00
1.3.42		Overheads, charges and profit on item 1.3.38 above	%	100000		
1.4	8.8	TEMPORARY WORKS (See 8.1.2.1 (d) )				
CARRIED FORWARD						

SECTION 1 : SABS 1200 A - GENERAL

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
		BROUGHT FORWARD				
1.4.1	8.8.1	Main Access Road to Works (construct and maintain)	Sum	1		
1.4.2	8.8.1	Construct Main Access Road to Completed Reservoir	Sum	1		
1.4.3	PSA 8.8.2	Dealing with traffic	Sum	1		
1.4.4	PSA 8.8.7	Contractor to provide "Construction Record" Information	Sum	1		
1.4.5				0		
TOTAL FOR SECTION 1 CARRIED FORWARD TO SUMMARY						

## SECTION 2 : SABS 1200 C - SITE CLEARANCE (PIPE ROUTE)

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
2.1	8.2.1	Clear and grub (i) Pipeline route (10m wide strip)	m	6250		
2.2	8.2.2	Remove and grub large trees and tree stumps of girth a) over 1 m and up to 2 m	No.	5		
2.3		b) over 2 m and up to 3 m	No.	5		
2.4	8.2.3	Remove and grub all trees and tree stumps regardless of girth	ha	0.5		
2.5	8.2.4	Reclear surfaces (only on instructions from Engineer)	m	100		
2.6	PSC 8.2.5	Take down existing fences	km	0.5		
	8.2.6	Clear hedge or fence or both where not scheduled separately				
2.7		(i) Hedges up to 2m high	m	50		
2.8		(ii) Reinstate Hedge	m	50		
TOTAL FOR SECTION 2 CARRIED FORWARD TO SUMMARY						

SECTION 3 : SABS 1200 D - EARTHWORKS (PIPE ROUTE)

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
	8.3.8	Existing Services				
	8.3.8.1	Location				
3.1		c) Excavate by hand in soft material to expose water / telkom / electrical service (LI)	m³	50		
	8.3.10	Topsoiling				
3.2		(i) Pipeline Route	m²	3905		
	8.3.11	Grassing or Vegetation Cover				
3.3		(i) Pipeline Route, outside of canelands	m²	975		
3.4	PSD 8.3.13	Erosion Control Berms	m²	50		
3.5	PSD 8.3.14	Sandbag Protection to pipe trench	No.	50		
3.6	PSD 8.3.15	Extra-over Sandbag Protection for Stabilization	No.	50		
TOTAL FOR SECTION 3 CARRIED FORWARD TO SUMMARY						



## SECTION 4 : SABS 1200 DB - PIPE TRENCHES

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
	8.3.1	Site Clearance and (if specified) Removal of Topsoil				
4.1	PSDB 8.3.1.C	c) Remove Topsoil				
		(i) 150mm	m <sup>2</sup>	3905		
4.2		(ii) 300mm (within canelands)	m <sup>2</sup>	975		
	8.3.2	Excavation				
		a) Excavate in all materials for trenches, backfill, compact, and dispose of surplus material				
		For pipes:				
		Up to and including 400mm diam. for total trench depth:				
4.3		Over 0 and up to 1m (LI)	m	1300		
4.4		Over 1m and up to 2m	m	3090		
4.5		Over 2m and up to 3m	m	60		
		b) Extra-over item (a) above for:				
4.6		1) Intermediate excavation	m <sup>3</sup>	3310		
4.7		2) Hard rock excavation	m <sup>3</sup>	10		
4.8		3) Hard rock excavation near residential buildings (Mounted hydraulic breaker where directed by the Engineer)	m <sup>3</sup>	160		
4.9		c) Excavate and dispose of unsuitable material from trench bottom (provisional)	m <sup>3</sup>	210		
4.10	8.3.2(b)	Excavate and dispose of unsuitable material from trench bottom within a 1km radius freehaul (Provisional)	m <sup>3</sup>	3970		
	8.3.3	Excavation Ancillaries				
	8.3.3.1	Make up deficiency in backfill material (provisional)				
4.11		a) from other necessary excavations on site	m <sup>3</sup>	2010		
4.12		c) by importation from commercial or off site sources selected by the Contractor	m <sup>3</sup>	250		
4.13	PSDB 8.3.3.1	d) Stabilised backfill (4% cement)	m <sup>3</sup>	435		
4.14	8.3.3.3	Compaction in road reserves	m <sup>3</sup>	180		
4.15	8.3.3.4	Overhaul				
4.16		a) Limited Overhaul (provisional)	m <sup>3</sup>	250		
4.17		b) Long Overhaul (provisional)	m <sup>3</sup> .km	250		
	8.3.4	Particular Items				
		a) Shore trench opposite structure or service				
4.18		(i) Existing houses and toilet structures	m	50		
CARRIED FORWARD						

SECTION 4 : SABS 1200 DB - PIPE TRENCHES

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
		BROUGHT FORWARD				
	8.3.5	Existing Services that Intersect or Adjoin a Pipe Trench				
		a) Services that intersect a trench				
4.19		i) Concrete pipe up to 1000 mm dia.	No.	2.5		
4.20		ii) Water pipe up to 400 mm dia.	No.	3.5		
4.21		iii) Electrical Cables	No.	3.5		
		b) Services that adjoin a trench				
4.22		i) Water pipe up to 400 mm dia.	m	50		
4.23		ii) Telkom Cables	m	10		
4.24		ii) Electrical Cables	m	10		
	8.3.6	Finishing				
	8.3.6.1	Reinstate road surfaces complete with all courses				
4.25		a) Gravel on shoulders and wearing course	m <sup>2</sup>	20		
4.26		c) Asphalt of thickness 30mm in roadway	m <sup>2</sup>	120		
TOTAL FOR SECTION 4 CARRIED FORWARD TO SUMMARY						

SECTION 5 : SABS 1200 L - MEDIUM-PRESSURE PIPELINES

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
	8.2.1	Supply, Lay and Bed Pipes Complete with Couplings				
		250 Diameter Pipes				
5.1		(i) 250mm diam. mPVC CL16 to SABS 966-2	m	2060		
		200 Diameter Pipes				
5.2		(i) 200mm diam. mPVC CL16 to SABS 966-2	m	1800		
		160 Diameter Pipes				
5.3		(i) 160mm diam. mPVC CL16 to SABS 966-2	m	1180		
		63 Diameter Pipes				
5.4		(i) 63mm diam. HDPe CL16 to SABS 533	m	1200		
	8.2.2	Extra-over 8.2.1 for the Supplying, Laying and Bedding of Specials Complete with Couplings				
		mPVC Double Socketed Bends CL16				
		160 Diameter Pipe Bends				
5.5		(i) 160 mm Ø 11¼° bend	No.	1		
5.6		(ii) 160 mm Ø 22½° bend	No.	4		
5.7		(iii) 160 mm Ø 45° bend	No.	2		
		250 Diameter Pipe Bends				
5.8		(i) 250 mm Ø 11¼° bend	No.	12		
5.9		(ii) 250 mm Ø 22½° bend	No.	5		
5.10		(iii) 250 mm Ø 45° bend	No.	1		
	8.2.3	Extra-over 8.2.1 for the Supplying, Fixing, and Bedding of Valves				
		Isolating Valve assembly complete as per detail on drawing no. PRJ040-CT1-C303				
5.11		i) 250 mm Ø ND, PN16	No.	2		
5.12		ii) 160 mm Ø ND, PN16	No.	1		
		Scour Valve assembly complete as per detail on drawing no. PRJ040-CT1-C302				
5.13		(i) 80 mm Ø ND off 160 mm Ø OD mPVC pipe, PN 16	No.	1		
5.14		(ii) 80 mm Ø ND off 250 mm Ø OD mPVC pipe, PN 16	No.	3		
		Air Valve assembly complete as per detail on drawing no. PRJ040-CT1-C301				
5.15		(i) 25 mm Ø ND, PN 16	No.	7		
5.16		(ii) 50 mm Ø ND, PN 16	No.	1		
5.17		(iii) 80 mm Ø ND, PN 16	No.	1		
CARRIED FORWARD						

SECTION 5 : SABS 1200 L - MEDIUM-PRESSURE PIPELINES

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R	
5.18	8.2.11	BROUGHT FORWARD Inlet chamber assembly complete as per drawing no. PRJ040-CT1-C312 i) 160 mm Ø ND, PN16	No	1			
5.19		Anchor / Thrust Blocks and Pedestals as per drawing no. PRJ040-CT1-C306 b) Concrete Grade 25MPa / 19mm	m³	9			
5.20		b) Formwork	m²	125			
5.21	8.2.13	Reinforced concrete thrust wall complete including excavation, concrete, rough formwork, flanged 1.5m long GMS puddle pipe as per detail drawing including steel to uPVC adaptors for mains testing at each end and every 500m for the following pipe size (concrete to extend both 200mm below invert and above crown of pipes) :  (i) 200mm dia mPVC	No	4			
5.22		Reinforced concrete thrust wall complete including excavation, concrete, rough formwork, flanged 1.5m long GMS puddle pipe as per detail drawing including steel to uPVC adaptors for mains testing at each end and every 1400m for the following pipe size (concrete to extend both 200mm below invert and above crown of pipes) :  (i) 160mm dia mPVC	No	1			
5.23		Valves and Hydrant Chambers etc Isolating Valve Chamber complete as per detail on drawing no. PRJ040-CT1-C303	No.	3			
5.24		Scour Valve Chambers complete as per detail on drawing no. PRJ040-CT1-C302	No.	4			
5.25		Air Valve Chambers complete as per detail on drawing no. PRJ040-CT1-C301	No.	9			
5.26		Inlet Chamber complete as per detail on drawing no. PRJ040-CT1-C312	No.	1			
5.27		PSL 8.2.16	Supply and install pipeline markers as per detail on drawing no. PRJ040-CT1-C307	No.	54		
5.28		PSL 8.2.17	Supply and install valve markers as per detail on drawing no. PRJ040-CT1-C307	No.	17		
5.29			Sundry Items  Supply, lay, bed and install concrete pipe sleeves for road crossings, inclusive of all items (viz. skids etc) necessary for pipe support through sleeve as per drawing No... Class 100D, Spigot and Socket type as per drawing no. PRJ040-CT1-C3 for:				
			(i) 600 mm ND Concrete Sleeve for 400 mm ND mPVC pipe	m	5		
CARRIED FORWARD							

SECTION 5 : SABS 1200 L - MEDIUM-PRESSURE PIPELINES

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
5.30		BROUGHT FORWARD (ii) 600 mm ND Concrete Sleeve for 215 mm ND mPVC pipe	m	5		
5.31		(iii) 600 mm ND Concrete Sleeve for 200 mm ND mPVC pipe	m	5		
TOTAL FOR SECTION 5 CARRIED FORWARD TO SUMMARY						

SECTION 6 : SABS 1200 LB - BEDDING: (PIPES)

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
6.1	8.2.1	Supply only of Bedding from Trench Excavation within 0.5km				
6.2		a) Selected granular material	m <sup>3</sup>	81.56		
6.2		b) Selected fill material	m <sup>3</sup>	57.07913		
	8.2.2	Supply only of Bedding by Importation				
	8.2.2.3	From commercial sources (Provisional)				
6.3		a) Selected granular material	m <sup>3</sup>	888.173...		
6.4		b) Selected fill material	m <sup>3</sup>	513.71217		
6.5		c) 19mm graded crushed stone	m <sup>3</sup>	200		
6.6	8.2.3	Concrete Bedding Cradle	m <sup>3</sup>	5		
	8.2.4	Encasing of Pipes in Concrete				
6.7		(i) Grade 25 MPa / 19 mm concrete	m <sup>3</sup>	7.5		
6.8	8.2.5	Overhaul of Material for Bedding Cradle and Selected Fill Blanket	m <sup>3</sup> .km	1500		
TOTAL FOR SECTION 6 CARRIED FORWARD TO SUMMARY						

SECTION 7 : 750KL ELEVATED TANK

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
7.1	SABS 1200 C 8.2.1					
7.1.1	PSC 3.1 PSDB 8.3.1.2	Clear and grub elevated tank base area including removing of existing trees, shrubs, rocks and debris as directed by the Engineer	m <sup>2</sup>	210		
7.1.2		Remove and grub large trees and tree stumps of girth over 0,5m and up to and including 1m	No	2		
7.1.3		over 1m and up to and including 2m	No	1		
7.1.4		over 2m and up to and including 3m	No	1		
7.1.5	8.2.10 PSC 3.1 PSDB 8.3.1.C	Remove topsoil to a depth of 150 mm prior to carrying out bulk excavation, stockpile and maintain for further use	m <sup>2</sup>	210		
7.2	SABS 1200 DB PSD	Bulk Excavations				
7.2.1	8.3.2	Excavate in all materials for structural steel tank stand base, and stockpile for later use and maintain for backfill and dispose of the remainder to an approved spoil site (including shaping to be free-draining and with embankment slopes shallower than 1:3 and compacting)		0		
7.2.2		a) Over 0m up to 2.0m	m <sup>3</sup>	420		
7.2.3		b) Over 2m up to 3.5m	m <sup>3</sup>	310		
7.2.4		Extra over for:				
7.2.5		Intermediate materials	m <sup>3</sup>	75		
7.2.6		Hard rock excavation	m <sup>3</sup>	75		
7.2.7	8.3.2 b.3	Boulder excavation Class A	m <sup>3</sup>	15		
		Restricted excavations: Excavate in all materials, and stockpile for later use and maintain for backfill and dispose of the remainder to an approved spoil site (including shaping to be free-draining and with embankment slopes shallower than 1:3 and compacting)				
7.2.8		Under floor slab	m <sup>3</sup>	235		
		Extra over for:				
7.2.9		Intermediate materials	m <sup>3</sup>	25		
7.2.10		Hard rock excavation	m <sup>3</sup>	25		
		Backfill:				
7.2.11		Backfill with material from stockpile Below ground level and compact to 95% Mod. AASHTO from excavation to form new levels	m <sup>3</sup>	235		
CARRIED FORWARD						

SECTION 7 : 750KL ELEVATED TANK

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
		BROUGHT FORWARD				
7.2.12	8.3.4	Imported Geo-fill below floor slab as directed.				
		Rip and recompact 150mm layer insitu material, stabilised with 2% lime and compact to 95% mod. Aashto dry density at O.M.C. below floor slab as directed by the engineer.	m <sup>2</sup>	210		
7.2.13		Import, place and compact in individual layers "G5" material to form Geo-fill below floor slab as directed by the engineer. Fill to be placed in layers typically 200 mm thick when loose and compacted to 97% Modified AASHTO dry density at O.M.C.	m <sup>3</sup>	165		
7.2.14		Import, place and compact in individual layers "G2" material to form Geo-fill below floor slab as directed by the engineer. Fill to be placed in layers typically 200 mm thick when loose and compacted to 98% Modified AASHTO dry density at O.M.C.	m <sup>3</sup>	70		
		Finishing				
7.2.15		Topsoil obtained from prescribed stockpile on site in grassed areas 100 mm thick	m <sup>2</sup>	175		
		Grassing				
7.2.16		Grassing with sods including watering, maintaining etc for the duration of the contract	m <sup>2</sup>	150		
7.3	SABS 1200 GA & PSG PSG 7.2.6					
		UNREINFORCED CONCRETE				
		15 Mpa / 26mm Concrete				
7.3.1	8.4.2	Blinding layer minimum 75 mm thick	m <sup>2</sup>	205		
	8.4.3	20 Mpa / 19mm Concrete				
7.3.2		Mass concrete in encasing inlet, scour and outlet pipes	m <sup>3</sup>	4		
	8.4.3 PSG 5.5.11 PSG 7.2.6	REINFORCED CONCRETE				
		30 Mpa / 19mm Concrete				
7.3.3		concrete base and concrete stubs	m <sup>3</sup>	308		
7.3.4		Column stubs	m <sup>3</sup>	5		
	8.2 PSG 8.1.1 8.2.2	FORMWORK				
	8.2.1	Rough Vertical to form				
7.3.5		.01 1500mm high shutter for sides of concrete base	m <sup>2</sup>	60		
CARRIED FORWARD						



SECTION 7 : 750KL ELEVATED TANK

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
7.3.6		BROUGHT FORWARD .02 1000mm high shutter for sides of concrete stubs	m <sup>2</sup>	30		
	8.4.4 (a) PSG 5.5.10.2	UNFORMED SURFACE FINISHES  Wood floated finish (to degree of accuracy II)				
7.3.7		Top of concrete base	m <sup>2</sup>	205		
	8.4.4 (b) PSG 5.5.10.3	Steel float finish				
7.3.8		Top of concrete stubs	m <sup>2</sup>	4		
	8.1.2	REINFORCEMENT				
	8.3.1	Mild steel bars				
7.3.9		(a) 8 mm	ton	0.5		
7.3.10		(a) 10 mm	ton	1		
		High - tensile steel bars				
7.3.11		(a) 12 mm	ton	15		
7.3.12		(b) 16 mm	ton	10		
7.3.13		(c) 20 mm	ton	6		
7.4	SABS 1200 HA	SUNDRY STEELWORK				
7.4.1		SECTIONAL STEEL TANK  Supply and install a 784kl bolted galvanised sectional steel tank on a 20m high galvanised structural steel tank support (tower). Rate to include internal and external ladders, hand rails and access platform. Lockable access hatch to prevent unauthorised access to the platform must also be provided. All Hot-dip galvanising to SANS 121 (ISO 1461).Rate to include water tightness testing, safety files & structural engineering certifiactes for the tank and tank support, etc.	Sum	1		
TOTAL FOR SECTION 7 CARRIED FORWARD TO SUMMARY						

SECTION 8 : PIPE JACKING

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
		Pipe Jacking Establishment				
8.1	8.2.1 a)	Fixed Charges DR08030	Sum	1		
8.2	8.2.1 b)	Fixed Charges Access road to Sindaweni	Sum	1		
8.3		Time Charges DR08031(Period to be stated by Tenderer) ..... Weeks	Sum	1		
8.4		Time Charges Access road to Sindaweni (Period to be stated by Tenderer) ..... Weeks	Sum	1		
8.5	8.2.2	Supply and Delivery to site of Jacking Pipes (ID600, Class 100D, Concrete Jacking Pipes	m	60		
8.6	8.2.3	Jacking of Pipes Complete, Includign the filling the voids with non organic, sand (ID 600 Class 100D, Concrete Jacking Pipes)	m	60		
8.7	8.2.4	Excavation for Jacking in all Materials (Hard Rock)	m <sup>3</sup>	30		
8.8		Construction of 460 mm thick , 700 width and 700mm high brick wall closure to ends of concrete jacked pipes following installation of bulk water pipeline and sleeves.	No	4		
TOTAL FOR SECTION 8 CARRIED FORWARD TO SUMMARY						

SECTION 9 : BOREHOLE DEVELOPMENT

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
9.1		Borehole Developments Including Pump House with concrete roof slab, Diesel Generator, Equiping the BH, Pump, all Mechanical and electrical components installed complete with pump controls, including geohydrological assesments, driling and all relevant testing with reports.	ProvSum	1	2 000 000.00	2 000 000.00
TOTAL FOR SECTION 9 CARRIED FORWARD TO SUMMARY						

SECTION 10 : SUBCONTRACTOR'S SCOPE

ITEM	PAYMENT REFERS	DESCRIPTION	UNIT	QUANTITY	RATE R	AMOUNT R
10.1	C3.3.2.1	Scope of mandatory subcontract works	Sum	1	6 600 000.00	6 600 000.00
TOTAL FOR SECTION 10 CARRIED FORWARD TO SUMMARY						

SECTION	DESCRIPTION	AMOUNT R
1	SABS 1200 A - GENERAL	R
2	SABS 1200 C - SITE CLEARANCE (PIPE ROUTE)	R
3	SABS 1200 D - EARTHWORKS (PIPE ROUTE)	R
4	SABS 1200 DB - PIPE TRENCHES	R
5	SABS 1200 L - MEDIUM-PRESSURE PIPELINES	R
6	SABS 1200 LB - BEDDING: (PIPES)	R
7	750KL ELEVATED TANK	R
8	PIPE JACKING	R
9	BOREHOLE DEVELOPMENT	R
10	SUBCONTRACTOR'S SCOPE	R
A	NETT TOTAL OF TENDER	R
B	ADD CONTINGENCIES 10.0% OF NETT TOTAL	R
C	TENDER AMOUNT	R
D	ALLOWANCE FOR CONTRACT PRICE ADJUSTMENT	R
E	ALLOWANCE FOR VAT AT 15.0%	R
F	TOTAL TENDER SUM	R