

**OR TAMBO DISTRICT MUNICIPALITY**

MTHATHA CENTRAL CORRIDOR REGIONAL BULK WATER SUPPLY – PHASE 1

CONSTRUCTION OF BULK GRAVITY MAIN FROM AREA 6 RESERVOIR TO LINDILE - CONTRACT 1

MIS 535 – 774 A

**SECTION 5 : BEDDING**

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R
<b>5</b>	<b>SANS 1200 LB</b>	<b>BEDDING - BULKLINE - CONTRACT 1</b>				
5,1	8.2.1	<u>Provision of Bedding from Trench Excavation</u>				
5.1.1	8.2.1 (a)	Selected granular material	m <sup>3</sup>	10 181		
5.1.2	8.2.1 (b)	Selected fill material	m <sup>3</sup>	6 787		
5,2	8.2.2	<u>Supply only of Bedding by Importation</u>				
5.2.1	8.2.2.1	<u>From other necessary excavations (Provisional)</u>				
5.2.1.1	8.2.2.1 (a)	Selected granular material	m <sup>3</sup>	3 054		
5.2.1.2	8.2.2.1 (b)	Selected fill material	m <sup>3</sup>	2 036		
5.2.2	8.2.2.3	<u>From Commercial sources</u>				
5.2.2.1	8.2.2.3 (a)	Selected granular material	m <sup>3</sup>	1 018		
5.2.2.2	8.2.2.3 (b)	Selected fill material	m <sup>3</sup>	679		
5,3	8.2.3	<u>Concrete Bedding Cradle (Provisional)</u>				
5.3.1		15/19 Grade concrete	m <sup>3</sup>	3		
5,4	8.2.4	<u>Encasing of Pipes in Concrete (Provisional)</u>				
5.4.1		Encasement of Pipe in 25/19 Grade concrete including all formwork and reinforcement (100kg steel per m <sup>3</sup> concrete) for water crossings. Refer to standard detail	m <sup>3</sup>	22		
5,5	8.2.4	<u>Thrust Blocks</u>				
5.5.1		Construct thrust blocks in 25/19 Grade concrete including all preparation work and formwork required. Refer to standard detail	m <sup>3</sup>	37		
5,6		River Crossing				
5.6.1		Construct river crossing including all preparation work and formwork required. Refer to standard detail	Prov Sum	1	R150 000,00	R150 000,00
<b>Total Carried Forward To Summary</b>						