

OR TAMBO DISTRICT MUNICIPALITY

MTHATHA CENTRAL CORRIDOR REGIONAL BULK WATER SUPPLY – PHASE 1
 CONSTRUCTION OF BULK GRAVITY MAIN FROM LINDILE TO TSHEMESE - CONTRACT 2
 MIS 535 774 B

SECTION 5 : BEDDING

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT R
5	SANS 1200 LB	BEDDING - CONTRACT 2				
5,1	8.2.1	<u>Provision of Bedding from Trench Excavation</u>				
5.1.1	8.2.1 (a)	Selected granular material	m ³	13 788		
5.1.2	8.2.1 (b)	Selected fill material	m ³	9 192		
5,2	8.2.2	<u>Supply only of Bedding by Importation</u>				
5.2.1	8.2.2.1	<u>From other necessary excavations (Provisional)</u>				
5.2.1.1	8.2.2.1 (a)	Selected granular material	m ³	4 136		
5.2.1.2	8.2.2.1 (b)	Selected fill material	m ³	2 758		
5.2.2	8.2.2.3	<u>From Commercial sources</u>				
5.2.2.1	8.2.2.3 (a)	Selected granular material	m ³	1 379		
5.2.2.2	8.2.2.3 (b)	Selected fill material	m ³	919		
5,3	8.2.3	<u>Concrete Bedding Cradle (Provisional)</u>				
5.3.1		15/19 Grade concrete	m ³	3		
5,4	8.2.4	<u>Encasing of Pipes in Concrete (Provisional)</u>				
5.4.1		Encasement of Pipe in 25/19 Grade concrete including all formwork and reinforcement (100kg steel per m ³ concrete) for water crossings. Refer to standard detail	m ³	22		
5,5	8.2.4	<u>Thrust Blocks</u>				
5.5.1		Construct thrust blocks in 25/19 Grade concrete including all preparation work and formwork required. Refer to standard detail	m ³	37		
5,6		River Crossing				
5.6.1		Construct river crossing including all preparation work and formwork required. Refer to standard detail	Prov Sum	1	R150 000,00	R150 000,00
Total Carried Forward To Summary						